Abstract Notification.

Notice is hereby given that sealed tenders will be received at the office of the Chairman, City Improvement Trust Board, Mysore up to 15th March 1917.

For particulars *vide Mysore Gazette*, dated the 15th February 1917, pages 128—129.

T. G. LAKSHMANA RAO,
Chairman.

MYSORE DIVISION.

Dated 13th February 1917.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 8th March 1917, for additions and alterations required in converting the Body Guard Lines into Quarters for Mysore City Police. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1917.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees five hundred in cash or Government promissory notes, as earnest money, and be superscried "Tender for additions and alterations required in converting the Body Guard Lines into Quarters for Mysore City Police," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for improving Body Guard Lines at Mysore.

Serial No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation	C. yd.	0 2 6	179	28
2	Concrete in chunam	C. ft.	0 3 0	1,397	261
3	Burnt brick in chunam	"	0 3 6	13,528	2,959
4	Dismantling brick masonry	"	0 0 3	2,190	35
5	Burnt stone slabs dressed and fixed	S. ft.	0 8 0	1,981	996
6	Chunam plastering	Sqr.	2 8 0	306 65	766
7	White and colour washing	"	0 4 0	305·65	76
8	Coping with burnt brick in chunam and chunam plastering ...	R. ft.	0 5 0	1,219	382
9	Teakwood work wrought and put up	C. ft.	4 0 0	251·90	1,007
10	Teakwood battened doors complete	S. ft.	1 4 0	1,845	2,306
11	Teakwood windows with iron bars, etc., complete ...	"	1 12 0	440	770
12	Teakwood ventilators with wire net or perforated sheet ...	"	1 4 0	73	97
13	Roofing with 1st class Mangalore tiles over teak reepers and etc., complete.	Sqr.	24 0 0	113·20	2,717
14	Mangalore ridge tiles set in mortar	R. ft.	0 6 0	555	209
15	Flooring with 1st class Mangalore tiles on 3" concrete and cement pointed.	Sqr.	24 0 0	62·80	1,508
16	Flooring with Cuddapah slabs over 3" concrete and cement pointed.	"	24 0 0	38·72	929
17	Flooring with gravel	C. yd.	1 0 0	...	...
18	Painting	Sqr.	4 0 0	65·25	261
19	Providing seats in latrine	each	1 0 0	87	87
20	Teakwood eave board (9" wide)	R. ft.	0 9 0	836	470
21	Providing gutters	"	0 8 0	435	218
22	Roofing with pukka terrace	Sqr.	28 0 0	25·92	725
23	Mangalore ventilating tiles	each	2 0 0	70	140
24	Removing the existing pot tiled roof and stacking, etc. ...	Sqr.	1 0 0	113·20	113
25	Parapet wall of brick in mortar (1½' height)	R. ft.	1 0 0	357	357
26	Cornice (9" thick)	"	0 10 0	357	224
27	Excavating the existing earthen floor to a depth of 2 feet and refilling with new gravel and forming the floor.	Sqr.	4 0 0	97·90	391
28	Unforeseen items and other sundry works	Lump sum Rs.			235
	Total ...	...	...	...	18,261
	Constructing screen walls that may be found necessary during execution.	Lump sum Rs.			650
	Grand Total ...	...	...	...	18,911

Y. ASWATHANARAYANA RAO,
Executive Engineer.